



PALAU PUBLIC UTILITIES CORPORATION

ADDENDUM No. 1 **RESPONSES TO RFI's** **PUCE25-003**

May 15, 2025

Additional Information:

Response to RFI's:

1. Is 400kW Prime Genset required as Open set going into the building or required in sound attenuated Enclosure

Response:

Set going into the plant building and required in sound attenuated enclosure

2. Can we supply online? Or submit proposal online

Response:

Yes, send your proposal directly to j.kurihara@ppuc.com

3. Engages in Performance bond, bid security etc. only for large projects. If bonding is required or not?

Response:

Performance bond and security bond requires only for all construction and as such, this RFP is supply, will not require but submission must comply with all requirements in the RFP under proposal details.

4. Confirm whether the required voltage is 480V, 3-phase or another standard preferred by PPUC? Or standard electrical specifications in Palau?

Response:

Required voltage is 440V, 3 phase

Peleliu Power Station Specs:

- *Single phase: 120/240V*
- *Three phases: Powerhouse generators produce (440V line to line to a step-up 13,800/7970V transformer) then to the grid*
- *Frequency: 60Hz*