

ENERGY FIJI LIMITED

ADDENDUM NO. 1

MR 98/2026: Preferred Contractor for EFL Power Pole Replacement in Central Division

Tender Reference	MR 98/2026
Addendum Subject	Area of Work and Area-Based Pricing
Issue Date	26/08/26
Tender Closing	Wednesday, 2 September 2026 at 4:00 pm

1. Purpose of Addendum

This addendum amends the tender area of work and the pricing requirements under Section 2 (Tender Overview) and Section 10 (Pricing Schedule) of the tender specification. All other tender requirements remain unchanged unless specifically amended by this addendum.

2. Amendment to Work Location

Replace the existing “Work location” requirement in Section 2 with the following:

Work Location: The works shall be carried out within the following four pricing areas in the Central Division:

- Area 1: Wailekutu Bridge to Matanipusi
- Area 2: Wailekutu Bridge to Nausori Bridge
- Area 3: Nausori Bridge to Korovou Town
- Area 4: Korovou Town to Navesau

3. Amendment to Pricing Schedule

Tenderers shall submit a separate VAT-exclusive unit rate for each pricing item in each of the four areas. Each area rate shall be fully inclusive of mobilisation, cartage of poles and materials from EFL Kinoya Depot to the work site and return, vehicle, driver, fuel, loading, securing, transportation, unloading, travel, access, logistics and all other operating costs applicable to that area. No separate cartage payment will be made by EFL.

4. Revised Area-Based Pricing Schedule

Item	Description / Scenario	Unit	Area 1 Wailekutu– Matanipusi (VEP FJD)	Area 2 Wailekutu– Nausori Bridge (VEP FJD)	Area 3 Nausori Bridge– Korovou (VEP FJD)	Area 4 Korovou– Navesau (VEP FJD)
1	Replace 10.2 m concrete pole, including excavation, installation, backfilling, compaction and reinstatement	Each				
2	Replace 11 m concrete pole, including excavation, installation, backfilling, compaction and reinstatement	Each				
3	Replace 10.2 m wooden pole, including excavation, installation, backfilling, compaction and reinstatement	Each				
4	Replace 11 m wooden pole, including excavation, installation, backfilling, compaction and reinstatement	Each				
5	Replace 15.5 m wooden pole (single pole structure), including excavation, installation, backfilling, compaction and reinstatement	Each				
6	Replace 17 m wooden pole (single pole structure), including excavation, installation, backfilling, compaction and reinstatement	Each				
7	Replace/install H-pole structure, including poles, cross members, bracing, fittings, alignment, insulators and associated hardware	Structure				
8	Manual pole erection where crane/cherry picker access is not available (10.2 m poles)	Each				
9	Manual pole erection where crane/cherry picker access is not available (11 m poles)	Each				
10	Manual pole erection where crane/cherry picker access is not available (15.5 m poles)	Each				
11	Manual pole erection where crane/cherry picker access is not available (17 m poles)	Each				

Item	Description / Scenario	Unit	Area 1 Wailekutu– Matanipusi (VEP FJD)	Area 2 Wailekutu– Nausori Bridge (VEP FJD)	Area 3 Nausori Bridge– Korovou (VEP FJD)	Area 4 Korovou– Navesau (VEP FJD)
12	Manual pole erection where crane/cherry picker access is not available (All size H-pole structures)	Structure				
13	Remove and re-pull service main from existing pole and reconnect to new pole	Service				
14	Install ground stay, including excavation, installation, backfilling and reinstatement	Each				
15	Install fly pole and stay in accordance with EFL standards	Each				
16	Install anchor screw in accordance with EFL standards	Each				
17	Replace/reinstate pole earthing arrangement and lightning arrester on new pole in accordance with EFL standards	Each				

Pricing Clarification: Each area rate shall be complete and fully inclusive of cartage from EFL Kinoya Depot to the work site and return, together with all mobilisation, loading, unloading, travel, access, logistics and operating costs required for the applicable work item. No separate claim for cartage, distance travelled, fuel or transportation will be accepted. Rates shall remain firm for the contract period, subject to the tender conditions. EFL may award one contractor for all areas or different contractors for individual areas, based on the tender evaluation and EFL requirements.

Cartage Amendment: The separate cartage rate contained in Item 18 of the original tender pricing schedule is deleted and shall not be priced. Cartage shall be included in each applicable area-based unit rate.

Acknowledgement: Tenderers shall acknowledge receipt of this addendum and submit the completed revised area-based pricing schedule with their tender bid. Where this addendum conflicts with the original tender specification, this addendum shall prevail.